Abstract estimate for adding a room with a connecting corridoor to the Local Fund Dispensary at Saklespur.

Serial No.	Items of work	Per	Quantity
1	Earthwork excavation and filling foundation and basement.	C.yd.	26
2	Chunam jelly concrete	C.ft.	203
3	Size stone in mortar	,,	586
4	Burnt brick in mud	,,	749
5	Chunam plastering	Sqr.	14·65
6	Burnt stone slabs 6" thick dressed	S.ft.	104
7	Burnt brick in mortar	C.ft.	229
8	Teakwood pannelled door, complete	S.ft.	56
9	Do windows with glazed and pannel shutters, complete with iron bar and fitting.	,,	41
10	Dismantling wall and removing the existing window from the room and fixing a new door and rebuilding the sides of the same with brick in mortar and plastering, complete.	Each	1
11	Teakwood wrought and to put up with wood oiling, complete.	C.ft.	34·40
12	Roofing with 1st Class Mangalore tiles on teak reepers, complete.	Sqr.	5·30
13	Ridge tiles set in mortar	R.ft.	30
14	Flooring with Cuddapah slabs over 3" concrete and cement pointing, complete.	Sqr.	0·62
15	Flooring with 1st Class Mangalore tiles over 3" concrete and cement pointing.	,,	1·43
16	White and colour washing	,,	15·88
17	Chocolate painting two coats	,,	3·94
18	Teakwood ornamental eave board	R.ft.	98
19	Cement pointing to basement	Sqr.	1·23
20	Teakwood glazed ventilator, complete	S.ft.	21
21	Clearing site levelling ground	Lump	sum

R. L. STEELE,
Executive Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Dated 3rd May 1928.

Notice is hereby given that sealed tenders will be received at the Office of the General Superintendent, Generating Station, Sivasamudram, up to 2 P.M., on 25th May 1928, for constructing one Block of Line Inspector's Quarters with Out-Houses, Latrine and Stables at Ramapuram along the Metur Transmission Line. The tenders will be opened in public at 2 P.M., on Friday the 25th May 1928. The time required to complete the work and monthly progress should be indicated as these will be some of the chief factories in the award of tenders.

2. The plans, detailed estimate and conditions may be obtained at the Chief Electrical Engineer's Office, Bangalore, and also at the General Superintendent's Office, Sivasamudram, between the hours of 11 A.M. and 5P.M. on all working days.

3. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 75 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing one Block of Line Inspector's Quarters with Out-Houses, Latrine and Stables at Ramapuram along the Metur Transmission Line," in default of which, tenders will be rejected. 6 c

5. The final acceptance of any tender will rest with the General Superintendent, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The General Superintendent also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender, the successful tenderer will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the Notice Board in the General Superintendent's Office, Sivasamudram, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a fortnight from the date of notification of the acceptance.

10. Any other conditions that the contractor may wish to state should also be included in his tender.

11. Water for construction should be got at the contractor's own expense.

12. Specifications for work are those recognised by the Mysore Public Works Department and Marryot's Specifications.

13. The contractor should be bound by the conditions of the Schedule Contract of the Electrical Department.

Statement showing the approximate quantities of work for constructing one block of Line Inspector's Quarters with Out-Houses, Latrine, and Stables at Ramapuram along the Metur Transmission Line :—

Item No.	Items of work	Unit	Quantity
1	Earthwork excavation	C.yd.	54
2	Stone in clay foundation and basement	C.ft.	1875
3	Raw brick in clay superstructure	,,	3332
4	Stone slabs 6" roughly dressed	S.ft.	274
5	Mud plastering	Sqr.	67·53
6	Chunam pointing	,,	2·88
7	White washing two coats	,,	70·41
8	Flooring with 3" concrete and chunam plaster on top with a flushing coat of cement.	,,	10·77
9	Roofing with pot tiles on bamboo reepers with chunam patty on top.	,,	23·15
10	Country ridge tiles fixed in mortar	R.ft.	86
11	Jungle wood work wrought and put up	C.ft.	128·80
12	Jungle wood battened doors with fittings	S.ft.	300
13	Jungle wood battened windows with fittings including iron bars, etc., complete	,,	120
14	Chocolate painting 2 coats	Sqr.	20·02

B. D. NATH,
Ag. *General Superintendent,*
Sivasamudram.